

**THE PORT AUTHORITY OF NEW YORK AND NEW JERSEY
TWO MONTGOMERY STREET - 1st FLOOR
JERSEY CITY, NJ 07302**

May 1, 2018

ADDENDUM NO. 4

TO PROSPECTIVE BIDDERS ON CONTRACT **EWR-154.395** – NEWARK LIBERTY INTERNATIONAL AIRPORT – TERMINAL A REDEVELOPMENT PROGRAM BRIDGES N61, N62, N63, AT-GRADE ROADWAYS AND APPURTENANCES AND CONTRACT **EWR-154.395M** – NEWARK LIBERTY INTERNATIONAL AIRPORT – AGREEMENT TO PERFORM LANDSCAPE MAINTENANCE

The following changes are hereby made in the Contract Documents for the subject Contract.

This communication should be physically annexed to back cover of the book and initialed by each bidder before submitting his bid.

In case any bidder fails to conform to these instructions, his Bid will nevertheless be construed as though this communication had been so physically annexed and initialed.

CHANGES IN THE CONTRACT BOOKLET FOR CONTRACT EWR-154.395

- Page 3 - In the fifth line of D. in the clause entitled "Papers Accompanying Bids", delete "Proposals" and substitute therefor "Bids".
- Page 52 - Delete this page in its entirety and physically attach in its place new page 52 which is attached hereto and made a part hereof.

REVISED CONTRACT DRAWINGS

Drawings C3102, C3103, C3106, C3107, C4102, C4103, C4106, C4107 and C9602 have been revised as of 04/30/18. Drawings S0101, S0229 and S0321 have been revised as of 04/27/2018. Copies of these drawings are forwarded herewith on CD. Destroy the drawings of these numbers now in your possession and substitute therefor the revised drawings.

THE PORT AUTHORITY OF NEW YORK AND NEW JERSEY

James Starace, P.E.
Chief Engineer/Director

INITIALED BY THE BIDDER:

I. SCHEDULE OF UNIT PRICES FOR CLASSIFIED WORK				
Item No.	Estimated Quantities	Items of Classified Work With Unit Prices Written	Figures	
			Unit Prices	Amounts ²⁷
26	15,000 TONS	ASPHALT CONCRETE MIX PA-5 (PG 64-22), PER TON. _____ DOLLARS _____ CENTS		
27	10,400 TONS	PLANT MIX MACADAM, PER TON. _____ DOLLARS _____ CENTS		
28	10,500 C.Y.	DENSE GRADED AGGREGATE BASE COURSE, PER CUBIC YARD. _____ DOLLARS _____ CENTS		
ESTIMATED TOTAL FOR CLASSIFIED WORK ²⁸				

The following provisions are applicable to the Schedule of Unit Prices for Classified Work. The quantity for payment described in the following provisions shall be the quantity of Classified Work furnished, installed, performed and/or placed in accordance with the Specifications, as shown on the Contract Drawings and where ordered by the Engineer.

The definitions of "Work Hours A", "Work Hours E", "Work Hours I", "Work Hours J" and "NJDOT Lane Closure Hours" as used herein shall be as defined in Division 1 clause entitled "Hours of Work and Construction Staging".

No quantity of work will be included under more than one item of Classified Work.

In the case of Item No. 1 (Test Piles, Concrete Filled 18-inch O.D. x 0.5-inch Closed-Ended Pipe Pile), the quantity for payment shall be the number of linear feet of concrete filled 18-inch O.D. x 0.5-inch closed-ended test pipe piles actually installed. The length measured for payment shall be from the final as-driven tip elevation of the pile to the cut off elevation. The length of any test piles that do not conform to the requirements of the Contract Drawings and Specifications shall not be included in the length measured for payment, except that piles which do not conform to such requirements due to encountering an underground obstruction consisting of a rock, manufactured material or construction material as shown by the Contractor, and as determined by the Engineer on the basis of all field information, will be included in the quantity for payment.

In the case of Item No. 2 (Lateral Pile Load Test (Maximum Test Load: 20 Tons)), the quantity for payment shall be the number of lateral pile load tests actually performed, including materials, equipment and set-up, as shown on Contract Drawings GT0201 and GT0202.

²⁸ The Estimated Total For Classified Work shall be computed by totaling the amounts inserted in the "Amounts" column.