

**THE PORT AUTHORITY OF NEW YORK AND NEW JERSEY
TWO MONTGOMERY STREET - 1st FLOOR
JERSEY CITY, NJ 07302**

February 9, 2018

ADDENDUM NO. 5

TO PROSPECTIVE BIDDERS ON CONTRACT **JFK-184.010** – JOHN F. KENNEDY INTERNATIONAL AIRPORT – REPLACEMENT OF AIRPORT TRAFFIC CONTROL TOWER ROOFS, RELATED EQUIPMENT AND CURTAIN WALL REMEDIATION

The following changes are hereby made in the Contract Documents for the subject Contract.

This communication should be physically annexed to back cover of the book and initialled by each bidder before submitting his bid.

In case any bidder fails to conform to these instructions, his Bid will nevertheless be construed as though this communication had been so physically annexed and initialled.

CHANGES IN THE CONTRACT BOOKLET

Page 14- In the second and third lines of Clause 12, delete “James Brogan at (718) 244-3533 or email at jbrogan@panynj.gov” and substitute therefor “Alex Flores at (718) 244-4171 or e-mail at aflores@panynj.gov”.

Page 137 - Delete the third paragraph of Clause 110 in its entirety and substitute therefor “Electrical Power is not available at the construction site, except as specifically stated below. Provide temporary power for construction purposes and artificial lighting by use of portable generator(s) as approved by the Facility. The Contractor shall pay all costs of installation, maintenance, operation, removal and for service and power used.

Electrical Power is available at the construction site for the Contractor's sole use for the P/M Hoist Complex and its specific operation, subject to such conditions and precautions upon its use as may be imposed by the Engineer. The Contractor shall pay all costs of installation, maintenance, operation, metered power used and removal of temporary service connections for the P/M Hoist Complex as indicated in the Contract Documents.”

CHANGES TO THE CONTRACT DRAWINGS

Dwg. G103 - Delete General Note 35 in its entirety and substitute therefor "WATER IS AVAILABLE AT EACH ROOF LEVEL VIA A WALL HYDRANT. CONTRACTOR CAN CONNECT TO EXISTING WATER HYDRANT USING A FITTING. CONTRACTOR SHALL FURNISH AND INSTALL THE REQUIRED FITTING, METERS AND ANY REQUIRED BOOSTER PUMP(S) FOR THE WORK. CONTRACTOR SHALL PAY FOR ALL LABOR,

MATERIALS AND EQUIPMENT ASSOCIATED WITH THE WORK OF FURNISHING AND INSTALLING THE REQUIRED FITTING AND WATER METER AND WATER USAGE."

Dwg. G104 - Delete PERSONNEL AND MATERIALS (P/M) HOIST COMPLEX Note C.3 in its entirety and substitute therefor "FURNISH AND INSTALL A TEMPORARY PANELBOARD "NLT", LOAD CENTER, TRANSFORMER, TEMPORARY SCAFFOLDING CIRCUIT (200A CIRCUIT BREAKER - 150 A BREAKER FOR THE SCAFFOLDING AND PANEL "NLT" IS A 50A BREAKER FOR THE TEMPORARY COOLING UNITS FOR THE FAA ADMIN. 3RD FLOOR), AND SUB METER (IN ACCORDANCE WITH CONTRACT DRAWING E003) SOLELY FOR THE DEDICATED USE/OPERATION OF THE P/M HOIST COMPLEX. CONTRACTOR SHALL FURNISH AND INSTALL TEMPORARY TIE-INS, POWER CONNECTIONS, CONDUIT AND WIRING RUNS BETWEEN THE TEMPORARY PANELBOARD AND THE BOTTOM OF HOIST LOCATED ABOVE THE LEVEL 2 ROOF. CONTRACTOR SHALL PAY FOR LABOR, EQUIPMENT, USAGE METER AND MATERIAL COSTS ASSOCIATED WITH THE TEMPORARY INSTALLATION AND ITS EVENTUAL REMOVAL ONCE ALL CONSTRUCTION WORK IS COMPLETED. CONTRACTOR SHALL ALSO PAY FOR ALL COSTS ASSOCIATED WITH THE ELECTRICAL USAGE. THE CONTRACTOR SHALL FURNISH AND INSTALL LOCALIZED PORTABLE GENERATORS FOR ALL OTHER ELECTRICAL NEEDS WITH NOISE LEVELS NOT EXCEEDING 50 DECIBELS IN THE INTERIOR OF THE CONTROL TOWER."

THE PORT AUTHORITY OF NEW YORK AND NEW JERSEY

James Starace, P.E.
Chief Engineer/Director

INITIALED BY THE BIDDER:
